

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 08/23/13

CORNER DESIGNATION: 3N32, J19, The North One-Quarter Corner of Section 14.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under Contract 107, dated September 1864, notes state: Set post for 1/4 Sec. cor. in mound of Earth with charred stake pits & c as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R32E
1 S11
4 S14
2013
PLS 54657

MONUMENT SET: Reestablished corner at held intersection of field berms North and East as best available evidence of the original corner and set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with top 20" below ground level, marked as shown in "Monument Marking Detail", from which:

- A silver deep-1 magnet, buried 20" below ground, bears North 45 1/2° East, 27.7 feet.
 - A pink deep-1 magnet, buried 20" below ground, bears South 45° East, 35.5 feet.
 - A blue deep-1 magnet, buried 20" below ground, bears South 47° West, 33.1 feet.
 - An orange deep-1 magnet, buried 20" below ground, bears North 45 1/2° West, 32.2 feet.
- Buried bearing object tags with magnets.
Reset steel fence marking post 1.0 feet North of monument.

LOCATION AND COMMENTS: Corner falls at field intersection with berms North and East. There is an old steel field marker post near the corner monument.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N= 763133.85'
E= 8642115.15'

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS
Dean Roy

\3N32J19



RENEWS: 6-30-14