

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 05/07/04

CORNER DESIGNATION: L-9, The West One-Quarter Corner of Section 16, Township 3 North, Range 32 East, W.M., Umatilla County, Oregon.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner was originally established by David P. Thompson, under GLO Contract No. 106, dated August 16, 1864. Record states: Set post for 1/4 Sec. corner in mound of earth with charred stake, pits &c as per instructions. An undated, hand written sketch found in County Survey office files, notes "stone" at corner point. I suspect this map is from old Hayes and Harris files.

MONUMENT AND ACCESSORIES FOUND: Old North-South field berm and field and power line extending Easterly.

**MONUMENT MARKING DETAIL:**

T3N R32E  
1/4  
S17 | S16  
2004  
PLS 1106

MONUMENT SET: After verification by survey, I reestablished the corner point at the intersection of a old North-South field berm line and field and power line beginning 1/4 mile East and extending East to Highway 37. At the corner point, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe with cap buried 18" below the ground and marked as shown in "Monument Marking Detail".

**New Accessories:**

- A 3/4" brass washer stamped "PLS 1106", nailed 1.0 feet above ground level in a guy pole, bears North, 130.3 feet.
  - A silver deep-1 magnet buried 18" below ground level bears N 46° E, 39.2 feet.
  - A purple deep-1 magnet buried 18" below ground level bears S 39° E, 46.8 feet.
  - A blue deep-1 magnet buried 18" below ground level bears S 46° W, 47.8 feet.
- Buried bearing object signs with the deep-1 magnets.  
Attached bearing object sign to the guy pole accessory.

**LOCATION AND COMMENTS:**

Corner is located 150 feet South of Despain Gulch Road.

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT  
Marc Hammersla

\3N32L9

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-04*