

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla

DATE: 08-27-2012

CORNER DESIGNATION:

P-7, The Center Quarter Corner of Section 20, Township 3 North, Range 32 East, Willamette Meridian, Umatilla County, Oregon.


PREVIOUS RENEWALS / SURVEYS, ETC.:

No documents were found at the Umatilla County Surveyors Office showing any monumentation found or set at this corner position. The only reference to this corner is shown on the original General Land Office Plat for Township 3 North, Range 32 East, Willamette Meridian as surveyed by U.S. Deputy Surveyor, Daniel Chaplin, under contract No. 107 in 1864, the corner position is indicated by intersecting lines from opposite quarter corners as drawn by the draftsman.

MONUMENT AND ACCESSORIES FOUND:

Accepted the lone railroad tie fence post at the intersection of field lines running East-West and South as the best remaining evidence of the original corner position (this post was moved and reset approximately 2.0' North of new Aluminum Cap. See the 2012 J-U-B Engineers, Inc. Partition Plat for Tim Weidert for complete survey and corner details.

MONUMENT MARKING DETAIL:



MONUMENT SET:

Set 2-1/4" x 18" Aluminum pipe with a 3-1/4" Aluminum Cap with Deep-1 magnet in concrete, set flush with ground surface. The monument is approximately 2.0' South of the existing lone fence post. The Aluminum Cap is marked as shown above in the Monument Marking Detail.

NEW ACCESSORIES:

Set mag nail with red plastic washer stamped "JUB Control" in 6-0' tall lone railroad tie fence post, 1.0' above ground in South side of said fence post with bearing tag which bears N0°E, 1.62' from Aluminum Cap.

Set a 1/2" x 24" iron rebar with red plastic cap stamped "JUB Control", 24" below ground surface which bears S52°W, 7.56' from Aluminum Cap.

LOCATION AND COMMENTS:

The corner is located in a wheat field.

RECEIVED BY
Umatilla County Surveyor
Date: 7/10/12
Rec'd By: J. Oles
No.: 12-124-R

REFERENCE OBJECT MEASUREMENT PROCEDURE:

Reference bearings were obtained with a Silva Ranger Compass with a declination of 15° East.
Reference distances were measured using a 100-foot steel tape.

FIRM / AGENCY:

J-U-B Engineers, Inc.
2810 W. Clearwater Avenue, Suite 201
Kennewick, WA 99336
509-783-2144

WITNESSES:

Steven Day, Party Chief
Felipe Hernandez, Instrument Man

SURVEYOR'S SEAL

08-27-2012

REGISTERED
PROFESSIONAL
LAND SURVEYOR

John Joseph Shea
OREGON
JAN 10, 1996
JOHN JOSEPH SHEA
2751LS

RENEWAL DATE: 6-30-14

RECEIVED BY
Umatilla County Surveyor
Date: 9/10/12
Rec'd By: J. Shea
No.: 12-124-R