

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/11/13

CORNER DESIGNATION: 3N32, R19, The South One-Quarter Corner of Section 23.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under GLO Contract dated September 1864, notes state: Set post for quarter corner in mound of earth with charred stake & pits as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R32E
1 S23
4 S26
2013
PLS 54657

MONUMENT SET: Held the intersection of fence lines running North and West, with a field line South as the best remaining evidence of the original corner position and set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with top flush with the ground, stamped as stated in "Monument Marking Detail", from which:

A silver deep-1 magnet, buried 20" below ground, bears North 49° East, 29.7 feet.

A purple deep-1 magnet, buried 20" below ground, bears South 51° East, 26.9 feet.

A blue deep-1 magnet, buried 20" below ground, bears South 36° West, 26.5 feet.

An orange deep-1 magnet, buried 20" below ground, bears North 63° West, 22.1 feet.

Buried bearing object signs with magnets 20" below ground level.

Attached witness post sign to cut off power pole 1.0 foot North of monument.

LOCATION AND COMMENTS: Located 1 foot South of a 12" diameter cut off power pole marking field corner, with a newer fence North & West & field line South. New fence running North starts approximately 2.0 feet East of corner.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N= 752537.52'

E= 8642294.96'

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS
/3N32R19

