

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/30/13

CORNER DESIGNATION: 3N32, X21, The West One-Quarter Corner of Section 36.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under GLO Contract dated September 1864, notes state: Set stone 14 x 8 x 6 for 1/4 Sec. Cor. Acceptable corner evidence was noted as found on Survey No. 06-606-C, notes state: Intersection of County Road center lines to the West and North and a fence line to the South.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R32E
1/4
S35|S36
2013
PLS 54657

MONUMENT SET: Accepted the corner evidence as noted on Haddock Survey No. 06-606-C and at the intersection of County Road center lines to the West and North, and a fence line to the South, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, 4" below ground, stamped as stated in "Monument Marking Detail", from which:

A 3/4" brass washer stamped "PLS 1106", in railroad tie gate post bears North 26° East, 8.2 feet.

A 3/4" brass washer stamped "PLS 1106", in railroad tie gate post bears South 1/2° West, 20.2 feet.

A 3/4" brass washer stamped "PLS 1106", in railroad tie gate post bears South 55° West, 36.4 feet.

A 3/4" brass washer stamped "PLS 1106", in 8" green fence post bears North 53° West, 62.4 feet.

Attached bearing object signs to all wood posts by brass washers.

LOCATION AND COMMENTS: Located at the projection of Campbell Road North and West, at field road entrance.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N= 744679.59'

E= 8645076.29'

FIRM: Wells Surveying

P.O. Box 1696

Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS

Dean Roy

/3N32X21

