

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


T 2N , R 32E. , W.M.

Corner Code No. A-15

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by D. Thompson, U. S. Deputy Surveyor, under Contract No. 106, dated August 16, 1884. The original notes state that at the corner a wood post, with charred stake, earth mound and pits was set for the corner.



Corner No.
Compass Declination: 18.0

Description of corner evidence found:

None. The corner position falls in a wheat field.

Description of monument and accessories | established to perpetuate the original location of this corner:

This corner was reestablished by single proportion measure between the reestablished N.E. corner of Section 3 and the N.W. corner of Section 4 using the record proportional distances from Original Contract No. 106.

To reference this corner monument, I established two reference monuments in the east side of the access road leading to the City of Pendleton's North Hill High Level Reservoir. From the new corner monument:

A 1 1/2" plastic cap marked "W.R. Wells PLS 1106", set on a 5/8" by 30" iron rod bears S0°23'30"E 517.30'. This reference monument is in the east edge of the reservoir access road. The plastic cap is slightly below road level. An aluminum nail in top center of sawed off Pole No. 035970, bears S86°W 15.29'.

A 1 1/2" plastic cap marked "W.R. Wells PLS 1106", set on a 5/8" by 30" iron rod bears S0°23'30"E 724.41'.

The reestablished corner monument is a 2 1/2" brass cap on a 1 1/2" by 30" galv. iron pipe. The top of the corner monument is buried 18" below the top of the wheat field.

No steel fence post or signs were installed for the corner or reference monuments.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)