

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. A-19


Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by D. Thompson, U.S. Deputy Surveyor, under Contract No. 106, dated August 16, 1864. The original notes state that at the corner a wood post, with charred stake, earth mound and pits was set for the corner.

Record of Private Surveys, Book 1, located in the County Surveyor's Office, at Page 318, shows a statement by John Kimbrell, that he made surveys and set corners for Section 2 and Section 1 as shown on Page 310. Page 310 shows a measurement of 80.09 chains across the north line of Section 2, so possibly Kimbrell had reestablished the corner prior to 1895.

This corner position was reestablished by Terry Haaby, as part of a survey shown on Map No. R-23-B.



Corner No.
Compass Declination: 18.0

Description of corner evidence found:

Found 3" brass cap on a 2 1/2" galv. iron pipe, protruding 8" from the ground. The corner is located near a north-south fence line. The north-south fence has an east-west jog near the corner monument.

Description of monument and accessories I established to perpetuate the original location of this corner:

Cleaned up around the monument and made an earth mound. Referenced the existing monument as follows. From the existing monument:

A 1" iron bar, protruding 8" out of the ground bears N84°E 4.50'.

An aluminum nail in the N.W. corner of a railroad tie bears S48°W 1.42'. The nail is 8" above ground. Attached bearing object sign to the railroad tie.

An aluminum nail in the north side of a railroad tie in a east-west fence line bears S89°W 59.90'. The nail is about 18" above the ground. Attached witness corner and bearing object sign to the railroad tie.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19....

..... by

(COUNTY OFFICIAL)

(DEPUTY)