

OREGON CORNER RESTORATION FORM

Section: 11, 12 Township: 3N Range: 33E
County: Umatilla Date: 2/8/2012

Corner Designation: 3N33G21

Quarter corner common to Sections 11, 12, T3NR33E.

| | |
|-------|-----------------------|
| _____ | Condition Report Only |
| X | Not Found |
| X | Remonumented |
| _____ | Unrecorded |
| X | Surveyed In |
| X | Referenced Out |


Previous Renewals / Surveys, etc.

Originally surveyed by Chaplin in 1864. He set a post in a mound of earth, with charred stake and pits. In 1885 Zahner set a 15" x 9" x 12" rock in an unnumbered Private Survey, as recorded in Book 1, pp. 98-99.

Monuments and Accessories Found: (Condition and Source):

None.

Diagram



FIELD LINE

ORANGE MAGNET

SFP

Sketch

SILVER MAGNET

BC

PINK MAGNET

BLUE MAGNET

NAD 83/91
OREGON STATE PLANE NORTH
INTERNATIONAL FEET

N766462.78
E8676309.74

Monument(s) Set (Procedures and Description):

A 1 1/8" x 30" galvanized iron pipe with 2 1/2" brass cap, stamped as shown above, 1.6' below the surface, with a witness post sign on a steel fence post to the West, outside of the wheat field. The corner location was reestablished by single proportionate method between neighboring corners to the North and South.

References Set:

- "Deep One" magnets by Berntsen.
- An orange magnet lies N 61° 40' W, 30.23', 1.6' deep.
- A silver magnet lies N 41° 15' E, 27.93', 1.7' deep.
- A pink magnet lies S 67° 55' E, 37.33', 1.6' deep.
- A blue magnet lies S 8° 40' W, 35.08', 1.5' deep.

Location and Comments:

The corner is located 1/2 mile South and 1/2 mile East of the intersection of Deining Rd. and the Helix Hwy., in an active wheat field.

Compass Declination

17° E

Surveyors Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. English

OREGON
JANUARY 11, 2005
ROBERT DOUGLAS ENGLISH
43406LS

RENEWAL DATE: 12/31/13

RECEIVED BY:

Firm / Agency

Date: 2/10/2012
Rec'd By: A. Res
No. 12-094-C

Survey One, LLC.
P.O. Box 382
Pendleton, OR 97801
(541) 276-2055