

OREGON CORNER RE-ESTABLISHMENT FORM

COUNTY: Umatilla DATE: 06/12/97

CORNER DESIGNATION: Z-13, The Southwest Corner of Section 34, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by W. H. Odell, GLO Contract No. 114, dated July 2, 1866.

Notes state:

Set post corner for Secs. 3, 4, 33 and 34, drove charred stake, dug pits, and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Re-established corner location at the projection of a road heading North and the Westerly projection of a field berm extending East.

MONUMENT MARKING DETAIL:

T4N R35E
S33 | S34
S 4 | S 5
T3N R35E
1997
PLS 1106

MONUMENT SET:

Set a 2 1/2" brass cap on 1" x 30" galvanized pipe flush with the ground, cap marked as shown in Monument Marking Detail.

Accessories:

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 89° E, 14.2 feet.

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 54° W, 12.8 feet.

A brass washer stamped "PLS 1106" nailed to Pacific Power and Light pole #049002 bears N 84° W, 44.4 feet.

A brass washer stamped "PLS 1106" nailed to Pacific Power and Light pole #339002 bears N 21° W, 41.3 feet.

Iron rods have a bearing object attached and a steel fence post nearby with witness sign attached.

Power poles have witness and bearing object signs attached.

LOCATION & COMMENTS: The monument is located approximately 6 feet Southeast of the edge of an unimproved road heading West and North.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Kelly Snively
Jason Wells

OREGON STATE PLANE NORTH CO-ORDINATE FOR CORNER, NAD 83(91), INT. FEET:

N: 775610.26

E: 8728702.09

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-98