

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 9/21/95

CORNER DESIGNATION: V-21. Northwest corner Section 36, T3N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Nolin under Special Instructions dated May 4, 1887. Surveyor General Notes state: Set a stone 12x10x8 ins. 8 ins. in the ground for cor. to Secs. 25,26,35 & 36. And raised a mound of stone over cor. Pits impracticable. Re-established by C.E. Redfield in 1918, notes state: A stone mkd 11111 on N & 1 on S.

MONUMENT AND ACCESSORIES FOUND: A 17" x 10" x 9" basalt stone with a distinct groove on one face. A scattered 5 foot diameter mound of stone lying 3 feet West of stone.

MONUMENT SET: At position of found stone set a 5/8" x 30" iron pin with yellow plastic cap marked "OR PLS 1106, WA PLS 17372", projecting 6", with a 2 foot diameter mound of stone, GLO stone placed on North side of monument

New Accessories:

An "XBO" chiseled in rock outcrop bears N 42° E, 20.1 feet.
A 5/8" x 30" iron pin with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 44° E, 12.6 feet.
A 5/8" x 30" iron pin with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 51° W, 12.9 feet.
An "XBO" chiseled in rock outcrop bears N 40° W, 21.0 feet.
Attached bearing object tag to each iron pin, and set steel fence post alongside with survey monument sign attached.
A bearing object tag was nailed to crack in rock at each bearing object.

LOCATION & COMMENTS:

Corner falls approximately 1300 feet Northeast off the mouth of Squaw Creek on steep South facing hillside.

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Witness: William L. Hanley, PLS
Rod Lewis, LSIT

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will-R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-98

RECEIVED BY

Umatilla County Surveyor

Date 7-96

Rec'd By KK

No. 96-126-B