

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


CORNER TO SECTIONS 14, 15, 22 & 23, T 3N, R 36E

N-17
T 3N R 36E

History of original corner establishment:

ESTABLISHED BY G. S. PERSHIN UNDER HIS CONTRACT NO. 305, DATED SEPT. 20, 1878. HIS NOTES READ AS FOLLOWS:

NORTH BETWEEN SECTIONS 22 AND 23
79.50 SPRING BRANCH, COURSE S.E.
80.00 SET STONE 16x10x6 ON S.W. HILLSIDE ABOVE RAVINE FOR CORNER TO SEC. 14, 15, 22 AND 23. DROVE STAKE AND RAISED MOUND OF STONE AROUND STONE AND STAKE IN LIEU OF PITS.



Description of corner evidence found:

NO EVIDENCE FOUND.

Description of monument and accessories established to perpetuate the original location of this corner:

AT A POINT 50 LINKS (33 FT.) NORTH OF A CREEK, COURSE S.E., AS CALLED FOR IN ORIGINAL G.L.O. NOTES, AND AT AN E-W POSITION DETERMINED BY PROPORTIONAL DISTANCES FROM THE N. 1/4 COR. SEC. 23 AND THE CORNER AT THE INTERSECTION OF THE UMATILLA INDIAN RESERVATION BDDY. WITH THE LINE BETWEEN SECTIONS 16 AND 21, I SET A 2" x 30" ALUMINUM PIPE WITH 2 1/2" AL. CAP, MARKED AS SHOWN, 26" IN GROUND, IN A MOUND OF STONE.

FROM WHICH MY NEW BT:

A 20" PINE, SCRIBED "T3N R36E S 23 BT" BEARS S 16 3/4° E, 186.3 FT.

T 3N R 36E	
S 15	S 14
S 22	S 23
1986	
LS 934	

NO TREES WITHIN LIMITS IN OTHER SECTIONS.

REGISTERED PROFESSIONAL LAND SURVEYOR

Victor M. Moling

OREGON JULY 17, 1970 VICTOR M. MOLING 934

RECEIVED BY Umatilla County Surveyor Date 7-8-86 Rec'd By KA No. 84-82-M (86-37-B)

Office of..... County of..... State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19..... by..... (COUNTY OFFICIAL) (DEPUTY)