

OREGON PUBLIC LAND CORNER REPORT / RESTORATION REPORT
Umatilla County Surveyor's Office

SECTION 19	TOWNSHIP 3N	RANGE 36E
COUNTY: Umatilla		DATE 6/20/08
CORNER DESIGNATION: O-4 Northeast 1/16 corner, section 19		(Please check one)
		<input type="checkbox"/> Condition Report Only
		<input type="checkbox"/> Not Found
		<input type="checkbox"/> Renewed
		<input type="checkbox"/> Unrecorded
		<input checked="" type="checkbox"/> Surveyed In
		<input type="checkbox"/> Referenced Out
Previous Renewals / Surveys, etc.		
This Corner was originally set in 1919 by U.S. Indian Services Surveyor, C.E. Redfield. Mr. Redfield's notes state that he set the Corner by running a line South from the East 1/16 Corner common to Sections 18 and 19 to the Found Center East 1/16 Corner that was set by Currin in 1889.		
Monument(s) & Accessories Found: (Condition & Source)		
No evidence of the Redfield Corner was found.		
Monument Detail:	Sketch:	
Monument Set (Procedures and Description):		
At the mid-point of a line from the Found Redfield East 1/16 Corner common to sections 18 and 19 and the Found Redfield Center East 1/16 Corner of Section 19, I set a 1 1/2" x 30" Galvanized Iron Pipe, 6" in the ground to refusal and surrounded with a mound of stone and earth.		
New Accessories:		
A Railroad Tie Fence post with a Bearing Tree Sign attached, Bears N60°E, 27.0 feet. A Railroad Tie Fence Post with a Bearing Tree Sign attached, Bears S30°W, 24.0 feet.		
Location & Comments:		Compass Declination:
The Corner falls in a Cattle Holding and Loading Pen on the North side of the Draw in an Old Homestead Area		19° East
Firm / Agency USKH Address: 5 N. Colville St., Walla Walla, Wa 99632		SURVEYOR'S SEAL
Party Chief Greg E. Flowers		
Notes		OREGON JUNE 30, 1997 GREG E. FLOWERS 02820LS RENEWS 12/31/09
Witness Damon Locke		6/30/08

08-112-c