


2-11

History of original corner establishment:

The original survey was made by George E. Pershin under contract No. 304, dated Sept. 19, 1878. He set a fir post on level for 1/4 sec. corner. He set the following bearing trees:
A tamarack 22" dia. bears N 30 E, 10 lks. dist.
A fir 6" dia. bears S 65 W, 11 lks. dist.



Description of corner evidence found:

I made an extensive search in the area of this 1/4 corner, but due to the area being heavily logged several times since the original corner was set, I found no trace of evidence of any kind for this corner, thus determined the 1/4 corner to be a lost corner.

Description of monument and accessories established to perpetuate the original location of this corner:

Upon determining there was no acceptable evidence for this 1/4 corner and accepting it to be a lost corner, I used proportionate measurements to re-establish the 1/4 corner common to sections 33 & 4, at which point I set a 2" galv. iron pipe with a 2 1/2" brass cap 3" above the surface of the ground from which I set new bearing trees as follows:
A fir 7" dia. bears N 52 E, 60.55 ft. scribed 1/4 S S33 BT.
A fir 9" dia. bears S 65 W, 40.66 ft. scribed 1/4 S S4 BT.

Cap Stamped
T 4 N R 37 E
1/4 S 33
S 4
T 3 N
1978



Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office
for record on the..... day of..... 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)