

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 37E., W.M.

Corner Code No. Z-15

Note: Monument marked as shown below

History of original corner establishment:


This corner was originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 304, dated September 19, 1878.

The original notes state:

Set fir post in small open glade on level for 1/4 Sec. Cor.

A pine 11 in. di. brs N 5°E 104 lks. dist.
A fir 8 in. di. brs S 14°E 135 lks. dist.

In 1978, Douglas M. Ferguson recovered a small stone mound in a small glade, and determined the stone mound to be the perpetuation of the original corner, after making ties to adjacent corners. See corner certificate No. G-738.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

A mound of 9 stones, approximately 2 1/2' in diameter, with a 6" nail set in the middle of the mound.

The mound is 6' East of an old, down, North-South fence.

A Boise Cascade location poster, nailed to a tree, bears N 77°W 35.7'. The tag reads "S 70°E 48 lks to corner, ERT, DG, RM".

Original bearing trees in the corner area were searched, without success, for approximately two hours, prior to remonumenting the stone mound.

Description of monument and accessories | established to perpetuate the original location of this corner:

At the position of the nail found in the center of the stone mound, I set a 2 1/2" brass cap on a 1 1/4" galvanized iron pipe, 18" in the ground to bedrock and surrounded with a mound of earth and stone.

Marked four new bearing trees:

- A 13" white fir bears N 69°W 32.6' scribed 1/4 S34 BT.
- A 5" ponderosa pine bears N 30°W 80.0' marked "X" and breast height and "BT" at base of tree.
- A 14" white fir bears S 41 1/2°E 74.7' scribed 1/4 S3 BT.
- A 12" douglas fir bears S 72 1/2°W 60.3' scribed 1/4 S3 BT.

Placed bearing object signs on the new bearing trees.

Set steel fence post South of corner and attached a witness corner sign.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....
 State of..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor
 Date 9-9-77
 Rec'd By JK
 No. 91-25-C