

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Corner established by George S. Pershin under G.L.O. contract number 304 dated Sept., 19, 1878.

Surveyor General's records state:

Set a fir post on level for 1/4 sec cor from which:

A fir 2 1/4" diam. bears N 54° E., 115 lks dist marked 1/4 S BT
A spruce 8" diam. bears S 15° W., 42 lks dist marked 1/4 S BT



2-23

Description of corner evidence found:

NONE

Description of monument and accessories established to perpetuate the original location of this corner

Set a brass cap 2 1/2" dia. on a 2" iron pipe 31" long 6" above the ground with a 6' steel fence post alongside with a sign 54-4 attached.

new bearing trees:

A fir 10" diam bears N 85° 30' W., 84.0 ft dist marked 1/4 S BT
A spruce 8" diam bears S 09° 30' E., 72.0 ft dist marked 1/4 S BT

Each BT has a sign 54-3 attached 6" below a band of red paint and has a brass washer marked RPE 2808 nailed flush with BT blaze.



Office of Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 26 day of August, 1976.
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)