

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 37E., W.M.

Corner Code No. Z-25

Note: Monument marked as shown below

History of original corner establishment:


This corner was originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 304 dated September 19, 1878.

The original notes state:

Set fir post 6 in square and 6 ft long on nearly level for corner to townships 3 and 4 North Ranges 37 and 38 East Willamette Meridian.

- A fir 38 in diam. brs N 58°E 55 lks dist.
- A fir 24 in diam. brs S 76°E 110 lks dist.
- A fir 30 in diam. brs S 38°E 45 lks dist.
- A fir 32 in diam. brs N 45°W 74 lks dist.

Record G-1236-R, by RPE 2808, in 1974 indicates a brass cap monument in place was found.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Found a 3" brass cap on a 2 1/2" iron pipe protruding 12" out of ground, from which:

A 42" white fir snag bears N 45°W, 48.8'. No remaining scribes. (original bearing tree).

A 42" white fir snag bears S 76°E, 72.6'. Scribes visible on chopped open blaze. (original bearing tree).

There is an existing East - West fence line 60' to the North.

NOTE: I find no record for the existing 3" brass cap on 2 1/2" galv. iron pipe in County Surveyor's Office Records.

Description of monument and accessories I established to perpetuate the original location of this corner:

Maintained monument by mounding with earth.

Marked 4 new bearing trees:

- A 6" white fir bears N 12 1/2°E, 31.8', scribed T4N R38E S31 BT.
- A 7" douglas fir bears S 89 1/2°E, 29.0', scribed T3N R38E S6 BT.
- A 15" white fir bears S 46 1/2°W, 34.3', scribed T3N R37E S1 BT.
- A 15" white fir bears N 71 1/2°W, 43.5', scribed T4N R37E S36 BT.

Attached bearing object signs to the new bearing trees. Old original bearing trees have U.S.F.S. bearing tree tags attached.

Set steel fence post South of corner with witness corner sign, U.S.F.S. Land Corner Monument sign and National Forest Boundary sign attached.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-9 (Land Corner Monument) to the back side of all bearing trees. Painted face of blaze and a 6" red band around each bearing tree.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by (DEPUTY)

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 9-91

Rec'd By RK

No. 9175-C

☆ GPO-790-276