

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N , R 37E. , W.M.

Corner Code No. Z-3

Note: Monument marked as shown below

History of original corner establishment:


This corner was originally established by W.H. Odell, U.S. Deputy Surveyor, under Contract No. 114, dated July 2, 1866.

The original notes state:

Set post corner for 1/4 section from which:

A larch 12 in diameter bears N 33° E, 12 links.
A larch 6 in diameter bears S 09° W 32 links.

In 1974, under Survey No. I-153-C, a 2" by 18" pipe was reportedly set at the re-established corner position.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Found badly disturbed 2 1/2" O.D. pipe. This pipe was disturbed by a large uprooted fir.

This position of the 2 1/2" O.D. pipe was rejected because it is S 01° 15' W, 6.46' from position based on single proportion measurement.

Description of monument and accessories established to perpetuate the original location of this corner:

Re-established corner position by single proportion measurement between the Southwest corner of Section 31 and the Southeast corner of Section 32 and set a 2 1/2" brass cap on a 1 1/4" by 30" galvanized iron pipe 42" in ground and surrounded with a mound of earth. Buried monument deep to get below uproot sluff dirt.

From the new monument:

A 17" white fir with a partly healed blaze, bears S 43° W, 31.0'. (Survey I-153-C).

A 16" white fir with a partly healed blaze, bears S 86° W, 29.5'. (Survey I-153-C).

Marked 2 new bearing trees:

A 9" Englemann spruce bears N 35° E, 5.9', scribed 1/4 S31 BT.
A 6" Englemann spruce bears N 47° W, 11.5', scribed 1/4 S31 BT.

Placed bearing object signs on all bearing trees.

Set steel fence post 3.1' West of corner and attached witness corner sign.

There is an East-West fence line 8' to the South.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 9-9-77

Rec'd By KK

No. 91-25-C

☆ GPO—798-276