


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

C-N 1/6 Cor. Sec. 2, T3N R37E

History of original corner establishment:

NO RECORD



§-19

Description of corner evidence found:

NONE

Description of monument and accessories established to perpetuate the original location of this corner:

SET A 2" x 30" ALUMINUM PIPE WITH 2 1/2" ALUMINUM CAP, MARKED AS SHOWN ABOVE, 24" IN GROUND, FROM WHICH:

- A FIR, 11" DIAM., SCRIBED "CN 1/6 S 2 BT" BEARS S 6° E, 8.9 FT.
- A SPRUCE, 15 1/2" DIAM., SCRIBED "CN 1/6 S 2 BT" BEARS N 75 1/4° E, 31.2 FT.

SET A STEEL POST 3' EAST OF CORNER, WITH SIGN 54-4.  
 PAINTED A RED BAND AROUND BOTH BT'S, AND ATTACHED SIGN 54-3 ABOVE BLAZE AND SIGN 54-4 TO BACK OF TREES.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

Victor M. McLeod

OREGON  
JULY 17, 1899  
VICTOR M. MCLEOD  
934

RECEIVED BY

Umatilla County Surveyor  
 Date 7-31-86  
 Rec'd By JA  
 No. 86-72-R

Office of... SURVEYOR... County of... UMATILLA...  
 State of... OREGON... I hereby certify that the within instrument was filed in this office for record on the... day of... , 19...  
 (COUNTY OFFICIAL) by (DEPUTY)