


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

C-S 1/16 CORNER, SEC. 1, T 3N R 37E

History of original corner establishment:

No RECORD



D-23

Description of corner evidence found:

None

Description of monument and accessories I established to perpetuate the original location of this corner:

SET A 2" x 30" ALUMINUM PIPE WITH 2 1/2" ALUMINUM CAP, MARKED AS SHOWN ABOVE, 24" IN GROUND, FROM WHICH:

- A LARCH, 8" DIAM., SCRIBED "CS 1/16 S1 BT" BEARS S 53 1/2° E, 33.7 FT.
- A LARCH, 9" DIAM., SCRIBED "CS 1/16 S1 BT" BEARS S 57 3/4° W, 8.5 FT.

SET A STEEL POST 3' SOUTH OF CORNER, WITH SIGN 54-4.
 PAINTED A RED BAND AROUND BOTH BT'S, AND ATTACHED SIGN 54-3 ABOVE BLAZE AND SIGN 54-4 TO BACK OF TREES.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Victor M. Mc Lind

OREGON
 JULY 17, 1970
 VICTOR M. McLIND
 934

RECEIVED BY
 Umatilla County Surveyor
 Date 7-31-86
 Rec'd By RA
 No. 86-99-R

Office of.....SURVEYOR..... County of.....UMATILLA.....
 State of.....OREGON....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by.....
 (COUNTY OFFICIAL) (DEPUTY)