


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established this survey.



D-25

Description of corner evidence found:

Description of monument and accessories I established to perpetuate the original location of this corner

Set a 2 1/2" brass cap on a 2" iron pipe 31" long at base of south side of a 14" fir with a 6' steel fence post 3' south with sign 54-4 attached. Placed sign 54-2 on north and west side of 14" fir.

from which:

A larch 13" diam. bears S 50° W., 51.75 ft. dist. marked S 1/16 S 1 BT with sign 54-3 attached 6" below a band of red paint and with a brass washer marked RPE 2808 nailed flush with BT blaze.



Office of Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 26 day of August, 1976
 by _____
 (COUNTY OFFICIAL) (DEPUTY)