


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N-11

History of original corner establishment:

1879, George S. Pershin, U.S. Deputy Surveyor, while surveying a portion of the township under General Land Office Contract No. 340 established the corner as follows:
Set Basalt Stone 17 X 10 X 5 on level river bottom for 1/4 Sec. cor.
A Fir 28 in. di. brs. N. 40° W. 25 lks dist
A Maple 6 in. di. brs. South 24 lks dist



1900, William E. Campbell, U.S. Deputy Surveyor, while retracing the south boundary of sections 13 - 18 and completing the subdivision of the township under General Land Office Contract No. 718 described the corner as follows:
The point for the 1/4 sec. cor. S bdy. of sec. 16 on heavily timbered bottom at base of mountain: after renewed search fail to find any trace of this old cor. and set an ironstone 15 X 12 X 8 ins. 10 ins. in the ground, for 1/4 sec. cor., marked 1/4 on N. face, from which
A Fir 48 ins. diam. bears N. 22 1/2° E. 39 lks. dist., marked 1/4 S.16, B.T.

Description of corner evidence found:

None

Description of monument and accessories established to perpetuate the original location of this corner:

Set at proportionate distance a 2 1/2" by 30" aluminum pipe, with a 3 1/4" aluminum cap, 20" in the ground, surrounded with a ring of stones, marked as shown, from which:
7" Ponderosa Pine, bears N. 70 3/4° E., 50.1 feet scribed "1/4 S16" "BT" on double blaze with 3/4" brass washer "RLS 2308" nailed to the lower blaze.
11" Ponderosa Pine, bears S. 71 1/4° E., 62.3 feet scribed "X" "BT" on double blaze with 3/4" brass washer "RLS 2308" nailed to the lower blaze.
3 1/2" BPA aluminum cap stamped "B/L AZ", set in concrete flush with the ground, bears N. 60°09' E., 316.4 feet. The BPA cap is located north of the river, 7 feet southwesterly of County Road 900. A yellow fiberglass post with "Survey Marker" decal, bears N. 60° W., 2.0 feet from the BPA cap.



DATUM: NAD83(1991)

STATE PLANE COORDINATES: Oregon North Zone in International Feet

Latitude Longitude Northing(y) Easting(x)
45°43'48.50948" North 118°12'04.78237" West 760650.670 8789015.494

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David A. Schlaich

OREGON
JULY 16, 1987
DAVID A. SCHLAICH
2308

RENEWAL DATE: 06/30/2006

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 20.....

..... by.....
(COUNTY OFFICIAL) (DEPUTY)