


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:  
Corner not previously established.



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Corner not previously established.

Description of monument and accessories I established to perpetuate the original location of this corner:

At a point on the Wilderness Boundary line at the East line of Section 36, 468.59 feet North of the E 1/4 corner, I set a 2 1/2" x 30" aluminum pipe with aluminum cap marked as shown, 30 inches in the ground, from which:

New Bearing Objects;

A 5/8"x30" iron pin with plastic cap marked BGA SURVEY MARKER bears N66°W, 22.64 feet  
A 1/2"x30" iron pin with plastic cap marked BGA MARKER bears S87°W, 22.22 feet

Set a steel fencepost approximately 5 feet Westerly with Land Survey Monument and Wilderness Boundary signs attached.

I hereby certify that the above corner point was perpetuated as hereon described on Sept. 10, 1992.

Witnesses: Jeff Petersen and Jim Bennett



REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Duane I. Griffith*

OREGON  
JULY 10 1964  
DUANE I. GRIFFITH  
644

I used a steel tape and magnetic compass in the establishment of new accessories. I used 20° East magnetic declination.

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 10-92

Rec'd By KK

No. 92-18-R

\*GPO-591-971, 1988