


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:
Corner not previously established.



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Corner not previously established.

Description of monument and accessories I established to perpetuate the original location of this corner:

At a point on the Wilderness Boundary line and on the East-West centerline of Section 36, 2621.05 feet west of the E 1/4 corner, I set a 2 1/2" x 30" aluminum pipe with aluminum cap marked as shown, 28 inches in the ground, from which:

New Bearing Trees;

- A 12 inch diameter Douglas Fir bears N53°E, 30.6 feet marked WB 928A BT
- A 13 inch diameter Douglas Fir bears S85°W, 15.4 feet marked WB 928A BT

Attached Bearing Tree and Land Survey Monument signs to the bearing trees.

Set a steel fencepost approximately 5 feet West with Land Survey Monument and Wilderness Boundary signs attached.

I hereby certify that the above corner point was perpetuated as hereon described on Sept. 7, 1992.

Witnesses: Jim Bennett, Jeff Petersen,
Rick Robinson and John Osterman



I used a steel tape and magnetic compass in the establishment of new accessories. I used 20° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19....
 by
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
 Umatilla County Surveyor
 Date 10-92
 Rec'd By RR
 No. 72-118-R

*GPO-591-971, 1988

WB 928A