


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner Monumented by William E. Campbell, under contract No. 918, in 1900. Stone 15"X12"X4", 10" in ground, mkd. CC on East face, with 5 grooves on North and 1 groove on South faces. Pine, 11" diam., S.29°E., 69 Links, marked T3NR37E S31BT Stone mound on stone ledge East of corner. Note: No restoration appears in County records



Description of corner evidence found:

Cornerstone with 5 notches, CC, in a stone mound, stone mound 6.0' East, 22" D.B.H. Ponderosa Pine, (11" diam.) S.29°E., 45.5', with scribes visible.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Clayton J. Martin


OREGON
JULY 18, 1980
CLAYTON-JESSE MARTIN
1910

Description of monument and accessories | established to perpetuate the original location of this corner:

Set a 2½" diam. brass cap in a 2"X30" iron pipe at Corner and buried Cornerstone alongside pipe, raised rock mound

C.J. MARTIN SURVEYING
2751 JUNIPER ST.
SWEET HOME, OR 97308

Cap Stamped



10" D.B.H. Douglas Fir, N.87°E., 33.5', Scribed T3NR37ES30BT, Set brass washer mkd. RPLS 1910 BTWN, B&T Both B.T.'s have red painted bands, B.T. tags and attention signs Steel fence posts East and West of monument with attention, monument and boundary signs attached

Office of Surveyor County of Umatilla
State of Oregon I hereby certify that the within instrument was filed in this office for record on the 30th day of September 1982
David Krumbein by Billy Shatto
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 9-82
Rec'd by BLS
No. 82-113-R