

USDA-FOREST SERVICE

Index

File No. J-13

T. 3 N. R. 38 E.  
Merid. WILLAMETTE

**CORNER RECORD (SEARCH)**  
(Ref. FSM 7151.4)


R.D. WALLA-WALLA  
N.F. UMATILLA

County UNION  
State OREGON

Tract or  
Survey No. NF UMATILLA

Cor.  
No. AP-460

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found a stone 18" by 8" by 7" with notches on one edge, just down hill of a large mound of stone.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

A stone 28" by 20" by 12" well marked and in place (RECORD N. 7 1/4° W., 5.75 chains) (1899 obliterated corner).

PHOTO IDENTIFICATION DATA

Photo No.:  
Filed At.:  
Object Ident.:  
Ident. By:

*Signature*

PLANE COORDINATE POSITION

State: OREGON Zone: NORTH  
X: 2,690,137.023 meters  
Y: 233,984.829 meters  
Datum: NAD83(1991)

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. of Hwy. 204 and spur road. 050 which is located on the southwest side of the highway across from the Spout Springs ski area, follow spur 050 southwesterly to its end. Then walk southerly approx. 1000 feet to the posted wilderness boundary. Then follow the boundary southeasterly to the corner which is located on a spur ridge.

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

09/1994

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set in place of the stone a 2 1/2" by 30" aluminum pipe, with a 3 1/4" aluminum cap, 12" in the ground and raised a mound of stone 2' in dia. by 1 1/2' high (placed stone on north side of monument). The cap is mkd. "T3N R38E S9 S10 S16 S15 RLS 2308 1994

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

6" Douglas Fir, N. 76 1/2° E., 85.4 ft., mkd. "T3N R38E S10""BT" on double blaze with 3/4" brass washer mkd. "RLS 2308" nailed to the lower blaze by the "BT" scribing.

5/8" X 24" rebar with 1 1/2" alum. cap, 17" in the ground, S. 37°23' E., 69.1 ft., mkd. "USDA-FS RM S15 69.1 FT 2308".

5/8" X 24" rebar with 1 1/2" alum. cap, 13" in the ground, S. 26°15' W., 66.6 ft., mkd. "USDA-FS RM S16 66.6 FT 2308".

AP-458, 3 1/4" aluminum cap set flush with the ground, N. 9°58' W., 57.63 ft., mkd. "NFU WILDERNESS AP-458 ELEV 5000 RLS 2308 1994".

Work Done By **D. Schlaich**

Title **Land Surveyor**

Date **09/1994**

State Registration No.  
or Agency

Certified Cor. Record Prepared ? **YES**

Filed At: **UNION**

Date **10/1994**

REMARKS

Index File No.

**J-13**

T.

**3 N.**

R.

**38 E.**

M.

**W.M.**

Tract or Survey No.

**NF UMATILLA**

Cor.

**AP-460**