


UNIFIED RECORD OF LAND CORNER MONUMENTATION

J-05
(200500)

History of original corner establishment:

1899, John W. Kimbrell. U.S. Deputy surveyor, while surveying the township under General Land Office Contract No. 700 established the corner as follows:
Set Basalt Stone 20 x 14 X 4 ins 15 ins in the ground for Cor of Secs 7-8-17 and 18 marked with 4 notches on S and 5 notches on E edges
from which:
a fir 5 ins diam bears N23 3/4°E 115 lks dist marked T3NR38ES8BT.
a fir 16 ins diam bears S25 1/2°E 184 lks dist marked T3NR38ES17BT.
a fir 8 ins diam bears S22°W 154 lks dist marked T3NR38ES18BT.
a fir 5 ins diam bears N25°W 112 lks dist marked T3NR38ES7BT.
NOTE: John Kimbrell's 1899 survey was rejected by the General Land Office.



1903, John W. Kimbrell. U.S. Deputy surveyor, while resurveying the township under General Land Office Contract No. 700 established the corner as follows:
Set boulder stone 18 X 10 X 9 ins, 12 ins in the ground for cor of secs 7, 8, 17 and 18 marked with 4 notches on S, 5 notches on E sides and raised mound of stone 2 ft base 1 1/2 ft high W of cor, pits impracticable.
From this cor, the old sec cor, a stone marked and witnessed bears N 470 lks dist. I destroy cor & marks on bearing trees.

Description of corner evidence found:

No Evidence of the 1903 corner was found, but I did find the following evidence of the 1899 obliterated corner:
1899 section 8 BT is now a 24" Fir Snag with fragmentary scribing visible on sawn open face.
1899 section 17 BT is now a 30" Fir with healed blaze.

Description of monument and accessories I established to perpetuate the original location of this corner:

At record bearing and distance from the 1899 corner position I set a 2 1/2" by 30" aluminum pipe, with a 3 1/4" diameter aluminum cap, set 9" in the ground, surrounded by rock mound 2 1/2" in diameter by 1 1/2" high, marked as shown, from which;
1899 corner point bears North, 310.20 feet (record North 470 lks.)

New References:

- 5" Fir bears N. 6 1/4° E., 178.7 feet, scribed "T3N R38E S8" "BT" on double blaze.
- RM, 5/8" by 24" rebar with red plastic cap marked "UMATILLA N.F.", set 20" in the ground, bears S. 63°52' E., 29.53 feet.
- 7" Fir bears S. 74 1/4° W., 245.6 feet, scribed "T3N R38E S18" "BT" on double blaze.
- 23" Fir bears N. 14 1/2° W., 204.1 feet, scribed "T3N R38E S7" "BT" on double blaze.



I set at the 1899 corner point using record distances from the recovered BT's a 5/8" by 24" rebar, with a 2" diameter aluminum cap, set flush with the ground, marked as shown, from which;
24" Fir Snag bears N. 25 1/2° E., 75.9 feet, with fragmentary scribing visible on sawn open blaze (record N. 23 3/4° E., 115 lks.).
30" Fir bears S. 25° E., 121.4 feet, with healed blaze (record S. 25 1/2° E., 184 lks.).



The new bearing trees have a 3/4 inch diameter brass washer stamped "RLS 2308" nailed to the lower blaze near the "BT" scribing.

REGISTERED PROFESSIONAL LAND SURVEYOR

David A. Schlaich

OREGON
JULY 16, 1987
DAVID A. SCHLAICH
2308

RENEWAL DATE: 06/30/2002

Work Performed By: David A. Schlaich (RLS 2308)
Witnessed By: Levi D. Hamby
Equipment: Topcon GTS-4 Total Station
Magnetic Declination 19' east
Date: September 31, 2000

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by.....
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor

Date 11-00
Swd by KE
No. 00-241-R