


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

North Fork Umatilla Wilderness
AP-734

History of original corner establishment:

1996, David A. Schlaich, Land Surveyor Umatilla National Forest, while surveying the boundary of the North Fork Umatilla Wilderness established the corner as follows:

Set on the crest of a ridge 100 feet northerly of and perpendicular to the centerline of road 3100-287, a 5/8" by 3/6" rebar, with 3 1/4" aluminum cap, flush with the ground, from which:
15" Englemann Spruce bears N. 53° E., 30.9 feet scribed "WB/734""BT".
21" Western Larch bears N. 58 1/2° W., 23.6 feet scribed "WB/734""BT".
Shamrock Spring bears N. 73 3/4° W., 160.7 feet.
The bearing trees are double blazed and have a 3/4" diameter brass washer stamped "RLS 2308" nailed to the lower blaze near the "BT" scribing.



Description of corner evidence found:

Found a 3 1/4" diameter aluminum cap, set flush with the ground, marked as shown, from which:
17" Englemann Spruce bears N. 53° E., 30.9 feet scribing "WB/734" "BT" visible on partially healed double blaze and 3/4" brass washer "RLS 2308" nailed to the lower blaze.
22" Western Larch bears N. 59° W., 23.6 feet scribing "WB/734" "BT" visible on partially healed double blaze.



Description of monument and accessories established to perpetuate the original location of this corner:

DATUM: NAD83(CORS96) (EPOCH:2002.0000)
STATE PLANE COORDINATES: Oregon North Zone in International Feet

Latitude Longitude Northing(y) Easting(x)
45°42'59.40883" North 118°05'39.90268" West 756474.377 8816453.067

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 16, 1987
DAVID A. SCHLAICH
2308

RENEWAL DATE: 06/30/2006

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 20.....

..... by.....
(COUNTY OFFICIAL) (DEPUTY)