

USDA-FOREST SERVICE

Index
File No.

CORNER RECORD (SEARCH)
(Ref. FSM 5151.4)

Tract or
Survey No.

**N.F. Umatilla
Wilderness**


Cor.
No. **AP-765**

T. 3 N. R. 38 E.
Merid. Willamette

R.D. Walla-Walla
N.F. Umatilla

County Umatilla
State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No.
Filed At.
Object Ident.
Ident. By

Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the junction of F.S. road 3100 and abandoned road 3100-287 walk northwesterly on the abandoned road (now a trail) approx. 4900 feet. From this point the corner is located approx. 100 feet west of the road.

PLANE COORDINATE POSITION DATA

State: Oregon Zone: North
X: 2,615,291.56'
Y: 753,046.51'
Datum: NAD 1927

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

10/1996

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set at a point 100 feet westerly of and perpendicular to abandoned road 3100-287, a 5/8" by 24" rebar, with a 3/4" aluminum cap, 23" in the ground, stamped "NFU WILDERNESS AP-765 RLS 2308 1996".

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

8" Lodgepole Pine, S. 11° E., 27.7 feet, scribed "WB/765" "BT".

33" White Fir, N. 45° W., 17.2 feet, scribed "WB/765" "BT".

BT's are double blazed and have a 3/4" brass washer stamped "RLS 2308" nailed to the lower blaze by the "BT" scribing.

Work Done By D. Schlaich Title Land Surveyor Date 10/1996 State Registration No. or Agency _____

Certified Corner Record Prepared? Yes No Filed At: _____ Date _____

REMARKS

Index File No.

T. **3 N.**

R. **38 E.**

M. **Willamette**

Tract or Survey No.

N.F. Umatilla Wild.

Cor. **AP-765 765**