

USDA-FOREST SERVICE
Index
File No.

T. 3 N. R. 38 E.
Merid. Willamette

CORNER RECORD (SEARCH)
(Ref. FSM 5151.4)

R.D. Walla-Walla
N.F. Umatilla

County Umatilla
State Oregon

Tract or
Survey No.

**N.F. Umatilla
Wilderness**

Cor.
No. **AP-799**

CORNER DIAGRAM



PHOTO IDENTIFICATION DATA

Photo No.
Filed At.
Object Ident.
Ident. By

Signature

PLANE COORDINATE POSITION DATA

State: Oregon Zone: North
X: 2,617,153.75'
Y: 749,334.57'
Datum: NAD 1927

DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

The corner is located at the head of a small approx. N. 25° W., 700 feet from the junction of F.S. road 3100 and abandoned road 3100-287.

Signature
D. Schlaich

Title
Land Surveyor

Division

Headquarters
S.O.

Date
10/1996

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set in a small draw 100 feet westerly of and perpendicular to the centerline of abandoned road 3100-287, a 5/8" by 24" rebar, with a 3 1/4" aluminum cap, set 23" in the ground, stamped "NFU WILDERNESS AP-799 RLS 2308 1996".

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

16" Western Larch, S. 30 1/2° W., 20.9 feet, scribed "WB/799" "BT".

18" White Fir, N. 20 1/2° W., 23.0 feet, scribed "WB/799" "BT".

BT's are double blazed and have a 3/4" brass washer stamped "RLS 2308" nailed to the lower blaze by the "BT" scribing.

Work Done By D. Schlaich Title Land Surveyor Date 10/1996 State Registration No. or Agency _____

Certified Corner Record Prepared? Yes No Filed At _____ Date _____

REMARKS

Index File No.

T. **3 N.**

R. **38 E.**

M. **Willamette**

Tract or Survey No.

N.F. Umatilla Wild.

Cor. **AP-799**