


Index

File No.

T. 3 N. R. 38 E.
Merid. WILLAMETTECORNER RECORD (SEARCH)
(Ref. FSM 7151.4)R.D. Walla Walla
N.F. UMATILLACounty UMATILLA
State OREGONTract or
Survey No. NF UmatillaCor.
No. AP-368

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

Signature

PLANE COORDINATE POSITION

State: Oregon Zone: North

X: 2,618,229.86'

Y: 770,476.55'

Datum: NAD1927.

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. of F.S. roads 3719 and 3719-070 travel southerly on road 3719-070 approx. 0.7 miles to a steel fence post, with a wilderness boundary sign, set in the center of the road. From this point descend a small draw Easterly., 800 feet to the corner.

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

07/1996

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set in a small draw at an elevation of 4400 feet a 5/8" by 24" rebar, with a 3 1/4" aluminum cap, flush with the ground, mkd. "NFU WILDERNESS AP-368 RLS 2308 1996"

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

16" Douglas Fir, S 46° E, 34.4 feet, mkd. "WB/368" "BT".

16" Western Larch, S 9 3/4° W, 42.3 feet, mkd. "WB/368" "BT".

BT's are double blazed and have a 3/4" brass washer mkd. "RLS 2308" nailed to the lower blaze by the "BT" scribing.

Work Done By **D. Schlaich**

Title **Land Surveyor**

Date **07/1996**

State Registration No.
or Agency

Certified Cor. Record Prepared ? **NO**

Filed At:

Date

REMARKS

Index File No.

T.

3 N.

R.

38 E.

M.

W.M.

Tract or Survey No.

NF Umatilla

Cor.

AP-368