

History of original corner establishment:

The original corner was set by John W. Kimbrell on July 13, 1903, under contract No. 700, as follows:

Set a basalt stone 18" x 12" x 7" marked with 2 notches on the south and 4 notches on the east sides, from which:

- A 8" fir bears N43°E, 84 links (55.44 feet).
- A 12" fir bears S6°E, 48 links (31.68 feet).
- A 16" pine bears S61°W, 62 links (40.92 feet).
- A 6" fir bears N58°W, 29 links (19.14 feet).

From this corner the old corner bears N8°W, 457 links. I destroy the old corner and the marks on the bearing trees.

Description of corner evidence found:

The corner stone is solidly set 8" into the ground in an up-right position. The stone is 16" x 12" x 7" and is marked with 2 faint grooves on the south face and 3 faint grooves on the east face, from which:

- A 26" Douglas-fir with double healed blazes bears N46°E, 51.8 feet.
- A 26" Douglas-fir with double healed blazes bears S1°E, 32.0 feet.
- A 27" Ponderosa Pine with double healed blazes bears S66°W, 41.1 feet.
- A 17" Douglas-fir with double healed blazes bears N54°W, 20.4 feet.


I measure N8°W, 302 feet from this corner and find the following bearing trees for the superceded corner set by Kimbrell in 1899: The NE and SE bearing trees are large, live fir trees with healed blazes. The NW bearing tree is a broken stump with axe marks visible on the defaced blaze. The SW bearing tree is gone.

Description of monument and accessories I established to perpetuate the original location of this corner:

Moving the corner stone aside, I set in it's place a 2 1/2" x 30" aluminum pipe 24" into the ground. A 3 1/4" aluminum cap is attached to the pipe and is marked as shown in the diagram, above. I bury the corner stone alongside the southwest side of the aluminum pipe and build a mound of stones around the pipe to the cap.

The bearing trees are signed with a "Bearing Tree" sign nailed above the blazes and a "Land Survey Monument" sign nailed to the back of the tree.

I hereby certify the above corner was perpetuated as hereon described on October 3, 1996. Magnetic declination: 19°E.



R-9

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Dennis L. Gaylord

OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Renews 6/30/97

Office of COUNTY SURVEYOR County of UMATILLA
State of OREGON I hereby certify that the within instrument was filed in this office
for record on the day of , 19.....

..... by
(COUNTY OFFICIAL)

(DEPUTY)

RECEIVED BY

Umatilla County Surveyor
Date 10-96
Rec'd by JK
No. 96-165-R