

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z - 15  
DIAGRAM

**History of original corner establishment:**

The original corner was established by George S. Pershin, deputy, (compassman) on October 20, 1871, under joint GLO contract No. 154, as follows:

Set a stone, 22" x 10" x 5", on east bank of brook for 1/4 section corner to sections 3 and 34, T. 2 & 3 S., R. 30 E.

T2S R30E  
1/4 S34  
S3  
T3S  
PLS 1636  
2002

**Original corner evidence recovered:**

Found the original corner stone solidly set 14" in the ground. The corner stone is 21" x 11" x 6" and is plainly marked "1/4" on the north face. The corner is approximately one chain WEST of Ely Creek.

**Monument and accessories established to perpetuate the original position of this corner:**

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 27" into the ground. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone along the north side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N21° E, 150.7 feet. This reference monument is east of Ely Creek.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S54° E, 114.8 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S19° W, 100.0 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N46° W, 145.9 feet.

I attach a "witness post" sign to a steel fence post 3 feet west of the corner.

I hereby certify this corner point was perpetuated as hereon described on February 5, 2002. Magnetic declination set in compass: 16° E.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
*Dennis L. Gaylord*  
OREGON  
JULY 14, 1978  
DENNIS L. GAYLORD  
1636

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on: \_\_\_\_\_

RECEIVED BY  
Umatilla County Surveyor  
Date 02-02  
Marked *KK*  
No. 02-42-R