


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

Z - 3  
DIAGRAM

**History of original corner establishment:**

The original corner was established by George S. Pershin, Deputy, on October 20, 1871, under GLO contract No. 154, as follows:

Set a stone, 20" x 8" x 7", on northwest hillside for the 1/4 section corner to sections 31 and 6.



**Original corner evidence recovered:**

Found the original corner stone solidly set but tipped to the north. The corner stone is 19" x 10" x 6" and is plainly marked "1/4" on the south face.

**Monument and accessories established to perpetuate the original position of this corner:**

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 27" into the ground. I bury the corner stone along the south side of the pipe and build a small mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

- A 5/8" x 24" iron rod, set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 NE", wired to the rod at ground level, bears N35° E, 101.4 feet.
- A 5/8" x 18" iron rod, set 17" into the ground, with a 3/4" brass washer, marked "PLS 1636 SE", wired to the rod at ground level, bears S70° 30' E, 79.5 feet.
- A 5/8" x 18" iron rod, set 17" into the ground, with a 3/4" brass washer, marked "PLS 1636 SW", wired to the rod at ground level, bears S33° W, 107.3 feet.
- A 5/8" x 18" iron rod, set 17" into the ground, with a 3/4" brass washer, marked "PLS 1636 NW", wired to the rod at ground level, bears N48° W, 82.3 feet.

I hereby certify the above corner point was perpetuated as hereon described on February 15, 2005. Magnetic declination set in compass: 17° E.  
NAD '83 UTM Zone 11 position: 5023187N, 332708E (plus or minus two meters).

  
*Dennis L. Gaylord*

Renews June 30, 2005

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY  
 Umatilla County Surveyor  
 Date 2-05  
 Rec'd By KK  
 No. 05-47-R