


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

C - 25  
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on October 28, 1878, under GLO contract No. 304, as follows:

Set a stone, 18" x 10" x 8", on south side of ravine for the 1/4 section corner.



Original corner evidence recovered:

Found the original corner stone solidly set 15" in the ground. The corner stone is 18" x 11" x 7" and is plainly marked "1/4" on the east face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 27" into the ground. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone along the west side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N29° 30' E, 59.4 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S58° E, 86.2 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S9° W, 32.3 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N56° 30' W, 50.3 feet.

A wire fence projecting northwest and southeast bears west, 26.5 feet.

I nail a "Witness Post" sign to a wood fence post 27 feet west of the corner.

The two easterly witnesses are east of, and across a draw from the corner.

I hereby certify the above corner point was perpetuated as hereon described on May 2, 2003. Magnetic declination set in compass: 19° E.

NAD '83 UTM Zone 11 position: 5022081N, 341622E (plus or minus two meters).

*Dennis L. Gaylord*  
REGISTERED PROFESSIONAL LAND SURVEYOR  
OREGON  
JULY 14, 1978  
DENNIS L. GAYLORD  
1836

Renews June 30, 2005

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY  
Umatilla County Surveyor  
Date 8-03  
Rec'd By KK  
No. 03-134-R