


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

E - 21  
DIAGRAM

**History of original corner establishment:**

The original corner was established by George S. Pershin on September 8, 1879, under GLO contract No. 332, as follows:

Set a basalt stone, 14" x 10" x 5", and a marked stake, in mounds of stone on the east side of a rocky spur for corner to sections 1, 2, 11 and 12.



**Original corner evidence recovered:**

Found the original corner stone solidly set 4" into the ground surrounded by a mound of small stones. The original corner stone is 15" x 12" x 9" and is plainly marked with one large notch on one edge. The marked stake of record is gone.

**Monument and accessories established to perpetuate the original position of this corner:**

In place of the corner stone, I set a 1" x 30" flared, galvanized iron pipe 24" into the ground. I bury the corner stone along the southeast side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S1", attached at ground level, bears N26° E, 77.4 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 12", attached at ground level, bears S39° E, 30.1 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 11", attached at ground level, bears S52° W, 118.9 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S2", attached at ground level, bears N75° W, 95.0 feet.

I hereby certify the above corner point was perpetuated as hereon described on February 6, 2004. Magnetic declination set in compass: 17° E.  
NAD '83 UTM Zone 11 position: 5021334N, 339949E (plus or minus two meters).



Renews June 30, 2005

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY  
Umatilla County Surveyor  
Date 2-04  
Rec'd By KK  
No. 04-40-R