


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J - 21
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 8, 1879, under GLO contract No. 332, as follows:



Set a basalt stone, 14" x 8" x 5", and a post in mounds of stone on the east side of ridge for corner to sections 11, 12, 13 and 14.

Original corner evidence recovered:

Found the original corner stone solidly set in the ground along with two other larger stones and surrounded by several small stones. The original corner stone is 14" x 10" x 5" and is plainly marked with two notches on the north edge and one notch/groove on the east face. The post of record is gone.

Monument and accessories established to perpetuate the original position of this corner:

In place of the corner stone, I set a 1" x 30" flared, galvanized iron pipe 23" into the ground. I bury the corner stone along the north side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 12", attached at ground level, bears N51° 30' E, 184.2 feet.
- A 5/8" x 24" iron rod set 22" into the ground with a 3/4" brass washer, marked "PLS 1636 13", attached at ground level, bears S29° E, 144.3 feet.
- A 5/8" x 24" iron rod set 22" into the ground with a 3/4" brass washer, marked "PLS 1636 14", attached at ground level, bears S72° W, 136.8 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 11", attached at ground level, bears N8° 30' W, 86.7 feet.

I hereby certify the above corner point was perpetuated as hereon described on April 30, 2004. Magnetic declination set in compass: 17° E.
NAD '83 UTM Zone 11 position: 5019723N, 339903E (plus or minus two meters).



Renews June 30, 2005

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
Umatilla County Surveyor
Date 5-04
Rec'd By KK
No. 04-90-R