


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z - 17  
DIAGRAM

**History of original corner establishment:**

The original corner was established by George S. Pershin, on November 3, 1878, under GLO contract No. 304, as follows:

Set a stone, 17" x 10" x 8", on a southwest rocky point for corner to sections 2, 3, 34 and 35, from which:



A 20 " pine bears S34° W, 322 links.

Finding an error in his earlier survey, George S. Pershin, on September 6, 1879, under GLO contract No. 332, conducted a resurvey of the township line, and at this corner he:

Set a basalt stone, 17" x 10" x 6", on the south side of a ridge for the corner to sections 34, 35, 2 and 3, from which:

- A 28" pine bears S45° E, 264 links (174.24 feet).
- A 28" pine bears S66° W, 264 links (174.24 feet).

This corner was made a corner of minimum control by the establishment of a closing corner for sections 2 and 3, a few days later in 1879, by George S. Pershin, under GLO contract No. 332.

**Original corner evidence recovered:**

Found the original corner stone solidly set in a mound of stones. The original corner stone is 19" x 10" x 9" and is plainly marked with two notches on the east edge, from which:

- A down and badly burnt Ponderosa Pine, no marks remaining, with charred stump which bears S43° E, 177.1 feet.
- An uprooted 40" Ponderosa Pine with partly healed and burnt blazes, chaining notch visible. Root hole bears S63° W, 177.5 feet

**Monument and accessories established to perpetuate the original position of this corner:**

In place of the corner stone, I set a 1" x 30" flared, galvanized iron pipe 22" into the ground. I bury the corner stone along the north side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

- A 5/8" x 24" iron rod, set 23" into the ground 4 feet north of a small quartz outcrop, with a 3/4" brass washer, marked "PLS 1636 35", attached at ground level, bears N32° E, 103.0 feet.
- A 11" Ponderosa Pine, scribed "T4S S2 BT", bears S55° 30' E, 179.0 feet.
- A 18" Ponderosa Pine, scribed "R30E BT", bears S5° 30' W, 165.8 feet.
- A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 34", attached at ground level, bears N46° W, 109.5 feet.
- I drive a steel fence post, with a BLM "K" tag attached, East, 0.5 feet of the corner.

RECEIVED BY  
 Umatilla County Surveyor  
 Date 5-04  
 Rec'd By KK  
 No. 04-92-R

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

Z - 17, T3S, R30E

The two new bearing trees are scribed on double blazes and have a 3/4" brass washer, marked "PLS 1636", nailed flush to the base of the lower blaze. Both new bearing trees have a "Bearing Object" sign nailed above the blazes and the new bearing tree to the southeast has a "Witness Post" sign nailed to the back side of the tree.

I hereby certify the above corner point was perpetuated as hereon described on April 30, 2004. Magnetic declination set in compass: 14° E.  
NAD '83 UTM Zone 11 position: 5013319N, 338076E (plus or minus two meters).



Renews June 30, 2005

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY  
Umatilla County Surveyor  
Date 5-04  
Rec'd By KK  
No. 04-92-B