

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z - 3  
DIAGRAM

History of original corner establishment:

This corner was originally established on November 2, 1878, by George S. Pershin under GLO contract No. 304. Pershin subsequently found an error in his survey, and on September 6, 1879, under GLO contract No. 332, he resurveyed this township line, and for this corner he:

T3S R30E  
1/4 S31  
T4S  
PLS 1636  
2000

Set a basalt stone, 12" x 10" x 8", on a southeast face of hill for the 1/4 section corner.

Original corner evidence recovered:

Found the original corner stone solidly set in a mound of small stones. The corner stone is 13" x 11" x 7" and is plainly marked "1/4" on top.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" galvanized, flared iron pipe, 24" into the ground. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I bury the corner stone along the west side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 36" iron rod, set 34" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N33°E, 87.9 feet.

A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S73° 30'E, 146.5 feet. This rod is 8" north of a steel fence post in a fence projecting northeast and southwest.

A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S45°W, 130.6 feet.

A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N58° 30' W, 112.6 feet.

A fence corner, with fences projecting east and southwest, bears east about 250 feet.

I hereby certify the above corner point was perpetuated as hereon described on August 15, 2000. Magnetic declination set in compass: 18°E.



Renews June 30, 2001

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

2000 AUG 21  
Umatilla County Surveyor  
8-00  
KF  
00-182-R