

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A - 13
DIAGRAM

History of original corner establishment:

The original corner was established by David P. Thompson on October 8, 1864, under GLO contract No. 106, as follows:

Set stone 24" x 18" x 12" for corner to sections 33, 34, 3 and 4.



Corner evidence recovered:

Found the original corner stone loosely set on the north edge of a mound of stones. The stone is 25" x 14" x 9" and is marked with three notches on one edge.

Monument and accessories established to perpetuate the original location of this corner:

In place of the original corner stone, I set a 1" x 30" iron pipe 13" into the ground to bedrock. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I bury the corner stone along the north side of the pipe and build a mound of stones around the pipe and over the cap, from which:

- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S34", attached at ground level, bears N17°E, 40.8 feet.
- A 5/8" x 36" iron rod set 30" into the ground and surrounded by a mound of stones, with a 3/4" brass washer, marked "PLS 1636 S3", attached at ground level, bears S64°E, 46.3 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S4", attached at ground level, bears S28°W, 41.9 feet.
- A 5/8" x 30" iron rod set 26" into the ground with a 3/4" brass washer, marked "PLS 1636 S33", attached at ground level, bears N43°W, 83.1 feet.

I hereby certify the above corner point was perpetuated as hereon described on June 15, 1998. Magnetic declination: 18°E.



Renews June 30, 1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1998.

RECEIVED BY

Umatilla County Surveyor
 Date 7-98
 Rec'd By XR
 No. 97-144-R