


History of original corner establishment:

The original corner was established by George S. Pershin on May 6, 1879, under contract number 319, as follows:

Set stone 16" x 12" x 10" on north slope for 1/4 section corner.



C-17

Description of corner evidence found:

Found a basalt stone, 14" x 12" x 11", solidly set in a large mound of stones and plainly marked "1/4" on the east face.

Description of monument and accessories established to perpetuate the original location of this corner:

In the exact position occupied by the corner stone, I set a 1 1/2" x 30" iron pipe, 22" into the ground. A 2 1/2" brass cap attached is marked as shown in the diagram above. I bury the corner stone along the south side of the pipe and build a mound of stones around the pipe to the cap, from which:

A 5/8" x 24" iron rod, set 22" into the ground with a 5/8" brass washer, marked "PLS 1636 S2", attached at ground level, bears S89° E, 48.4 feet.

A 5/8" x 24" iron rod, set 21" into the ground with a 1 1/2" aluminum cap attached, marked "PLS 1636 S2" with an arrow pointing toward the corner, bears S23° E, 46.3 feet.

A 5/8" x 24" iron rod, set 20" into the ground with a 5/8" brass washer, marked "PLS 1636 S3", attached at ground level, bears S72° 30' W, 55.9 feet.

A 5/8" x 36" iron rod, set 33" into the ground bears N24° 30' W, 36.0 feet.

I hereby certify the above corner point was perpetuated as hereon described on November 11, 1996. Magnetic declination: 20° E.

REGISTERED PROFESSIONAL LAND SURVEYOR

Dennis L. Gaylord

OREGON
JULY 14, 1996
DENNIS L. GAYLORD
1636

6/30/97

Office of COUNTY SURVEYOR County of UMATILLA

State of OREGON I hereby certify that the within instrument was filed in this office for record on the 11 day of NOVEMBER, 1996

..... by
(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 11-96
Paid By KK
No. 96-180-R