

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E - 11
DIAGRAM

History of original corner monumentation:

The original corner was established by George S. Pershin on May 14, 1879, under GLO contract No. 319, as follows:

Set basalt stone 16" x 10" x 8" on east slope for 1/4 section corner.



Corner evidence recovered:

The original corner stone is loosely set in a mound of stones. The stone is 16" x 11" x 9" and has plain, illegible chisel marks visible.

Monument and accessories established to perpetuate the original location of this corner:

At the point occupied by the original corner stone, I set a 1" x 30" iron pipe 19" into the ground. I bury the corner stone along the north side of the pipe and build a mound of stones around the pipe to the cap. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above, from which:

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level bears N43°30'E, 120.5 feet.

A 5/8" x 36" iron rod set 30" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level bears S43°E, 92.4 feet.

A 5/8" x 24" iron rod set 20" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level bears S46°W, 126.7 feet.

A 5/8" x 24" iron rod set 20" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level bears N38°W, 209.4 feet.

I hereby certify the above corner point was perpetuated as hereon described on March 29, 1998. Magnetic declination: 18°E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Dennis L. Gaylord

OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Renews June 30, 1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1998.

RECEIVED BY
Umatilla County Surveyor
Date 4-98
Rec'd By AK
No. 98-21-R