


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J - 5
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on May 17, 1879, under GLO contract No. 319, as follows:

Set a basalt stone 18" x 14" x 6" on the west face of spur. Drove a stake and raised a mound of stones around both.



Corner evidence recovered:

Found the original corner stone loosely set on the west edge of a mound of stones. The corner stone is 20" x 16" x 8" and is plainly marked with five notches on the east edge and two notches on the north edge. The original stake is gone.

Monument and accessories established to perpetuate the original location of this corner:

In place of the original corner stone, I set a 1" x 30" iron pipe 24" into the ground. A 2 1/2" brass cap attached to the iron pipe is marked as shown in the diagram above. I bury the corner stone along the west side of the iron pipe and build a mound of stones around the pipe to the cap, from which:

- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S8", attached at ground level, bears N28°E, 71.8 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S17", attached at ground level, bears S47°E, 71.3 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S18", attached at ground level, bears S47°W, 83.9 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S7", attached at ground level, bears N50°30'W, 89.3 feet.

I hereby certify the above corner point was perpetuated as hereon described on June 4, 1998. Magnetic declination: 18°E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Dennis L. Gaylord

OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Renews 6/30/99

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1998.

RECEIVED BY
Umatilla County Surveyor
Date 7-98
Rec'd By AK
No. 98-143-R