


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

L-25

History of original corner establishment: Corner was originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 304, dated September 19, 1878. The original notes state that at the corner a 4" dia Fir was marked from which:



- A 13" dia. Pine bears S56°E 28 LK dist.
- A 10" dia. Tamarack bears N50°W 7 lk dist.

No restoration appears in County Records.

Description of corner evidence found:

A 14" dia. tamarack bears N50°W 4.62 ft dist (old BT) fallen over. Visible scribing "S BT".

Description of monument and accessories I established to perpetuate the original location of this corner:

Measuring record bearing and distance from the center of the root hole at the base of the downed tree, I re-established the corner where I set:

A 2 1/2" brass cap on 2 1/2" x 30" l. pipe 20" in the ground with mound of stone from which:

- A 12" dia. W. Fir bears N19°W 30.0 ft dist marked: 1/4 S13 BT.
- A 9" dia. W. Fir bears S8°W 43.4 ft dist marked: 1/4 S13 BT.
- Blaze faces and 6" band around bearing trees are painted red. Trees tagged with 54- 3 and 4 signs.
- New BTs have lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush.

Set steel fence post, with 54-4 sign attached North of corner.
Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner monumented on October 18, 1982.


Cap marked:

Witnessed by: Leslie E. Wilson

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106



Office of..... County Surveyor..... County of..... Umatilla

State of..... Oregon..... I hereby certify that the within instrument was filed in this office

for record on the 15th day of December, 1982

David H. Krumbein, by Betty L. Shatto

(COUNTY OFFICIAL)

(DEPUTY)

RECEIVED BY
Umatilla County Surveyor GPO-798-276
Date _____
Rec'd by _____
No. 82-137-B