


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

L - 5  
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on May 17, 1879, under GLO contract No. 319, as follows:

Set basalt stone 15" x 12" x 7" on west side of spur extending north.



Corner evidence recovered:

Found the original corner stone solidly set. The corner stone is 16" x 14" x 10" and is plainly marked "1/4" on the west face.

Monument and accessories established to perpetuate the original location of this corner:

In place of the original corner stone, I set a 1" x 30" iron pipe 29" into the ground. A 2 1/2" brass cap attached to the iron pipe is marked as shown in the diagram above. I bury the corner stone to the west of the pipe and build a small mound of stones around the pipe and cap, from which:

- A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636", attached at ground level, bears N49°E, 62.5 feet.
- A 7" Ponderosa Pine, scribed "1/4 S17 BT", bears South, 31.7 feet.
- A 9" Ponderosa Pine, scribed "1/4 S18 BT", bears S83°W, 46.8 feet.
- A 12" Ponderosa Pine, scribed "1/4 S18 BT", bears N84°W, 105.8 feet.

The three bearing trees are scribed on double blazes, have a 3/4" brass washer, marked "PLS 1636", nailed flush to the scribed "B", a "Bearing Object" sign nailed above the blazes and a "Witness Post" sign nailed to the back of the tree.

I hereby certify the above corner point was perpetuated as hereon described on June 4, 1998. Magnetic declination: 18°E.

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

*Dennis L. Gaylord*

**OREGON**  
JULY 14, 1978  
**DENNIS L. GAYLORD**  
1636

*Renews 6/30/99*

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on \_\_\_\_\_, 1998.

**RECEIVED BY**  
Umatilla County Surveyor  
Date 7-98  
Rec'd By KK  
No. 98-142-R