

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N - 13
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on May 7, 1879, under GLO contract No. 319, as follows:

Set granite stone 16" x 10" x 8" on east side of ridge for corner to sections 15, 16, 21 and 22, from which:

T3S R31E
S16|S15
S21|S22
PLS 1636
1998

A 8" willow bears N48°E, 26 links (17.16 feet).

A 13" pine bears S44°E, 13 links (8.58 feet).

A 24" pine bears S58°W, 42 links (27.72 feet).

A 36" pine bears N30°W, 56 links (36.96 feet).

Each tree scribed with the township, range and section in which the tree stands, as well as "BT".

Corner evidence recovered:

The original corner stone is gone, apparently disturbed by logging or fence building activities. The original 24" pine is a fallen and decayed Ponderosa Pine. It is sawn off about 8 feet above the root crown. Full scribes for section 21 are visible. The root hole bears S58°W, 27.7 feet. The original 36" pine is a sawn and decayed Ponderosa Pine stump. Scribes for section 16 are visible on the lower portion of the original blazed face left on the stump. The stump bears N27°W, 37.0 feet. The other two bearing trees of record are gone.

Monument and accessories established to perpetuate the original location of this corner:

At the corner point as determined by reference to the two remaining original bearing tree remnants, I set a 1" x 30" iron pipe 27" into the ground. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above, from which:

A 6" Ponderosa Pine scribed "T3S R31E S15 BT" on double blazes bears N50°30'E, 44.6 feet.

A 13" Western Larch scribed "T3S R31E S22 BT" on double blazes bears S54°E, 22.0 feet.

A 11" Western Larch scribed "T3S R31E S21 BT" on double blazes bears S47°W, 69.1 feet.

A 15" Ponderosa Pine scribed "T3S R31E S16 BT" on double blazes bears N33°30'W, 70.0 feet.

Each new bearing tree has a "Bearing Object" sign nailed above the scribed blazes, a "Witness Post" sign nailed to the back of the tree and a 3/4" brass washer, marked "PLS 1636", nailed to the scribed "B". The two original bearing tree remnants described above have a "Bearing Tree" sign nailed to them.

I hereby certify the above corner was perpetuated as hereon described on May 7, 1998. Magnetic declination: 18° E.



Renews June 30, 1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1998. RECEIVED BY

Umatilla County Surveyor
Date 6-98
Rec'd By SR
No. 98-110-R