

BATTLE MOUNTAIN FOREST WAYSIDE

R 31E

Sec. 31

SECTION 31, T3S, R31E, W.M.
UMATILLA COUNTY
January 22, 1976

SURVEY NARRATIVE

The north, east and south section lines were located in the conventional manner and park corners established by deed description.

Section corners and quarter corners needed for this survey were tied by using a 300 ft. steel tape and a K & E Paragon 30-second optical plummet transit.

CORNER INFORMATION

SECTION CORNER 29,30,31, and 32

Var. 20 1/2°

Original:

Fir post 4" x 4" square 4' long, 2 ft. in ground (now missing)
20" pine N37°E, 122 LKS (now 32" pine)
24" pine S60°E, 140 LKS (now missing)
18" pine S68°W, 80 LKS (now missing)
20" pine N47°W, 73 LKS (now missing)

Restoration:

By County Surveyor

Found:

2 1/2" brass cap on 1 1/2" iron pipe and steel witness post.
32" pine N37°E 81.3 ft. scribed T3SR31ES29BT
12" pine N70°E 42.4 ft. scribed T3SR31ES29CSBT
12" fir S39°W 66.7 ft. scribed T3SR31ES31CSBT
28" pine N86°W 90.3 ft. scribed T3SR31ES30CSBT

Set:

Steel post with paddle marked, "OREGON STATE PARK BOUNDARY
Do Not Disturb," 2 ft. N.W. of corner

Witnessed by:

R. Hemmer
R. DePuy
C. Middleton

SECTION CORNER 25,30,31,and 36

Original:

Stone 14" x 10" x 4" in a mound of stone (found in place)

Restoration:

Set a 4" x 4" white post 1/2 ft. west of corner in mound of stone
with parks corner tag nailed to post.
Painted top of corner stone with flourescent orange paint.

Witnessed by:

J. Hollingsworth
R. Hemmer
R. DePuy
C. Middleton

QUARTER CORNER 30 and 31

Original:

Pine post (now missing)
14" pine North 115 LKS (now 16" rotten stump. Found chip
with "BT" visible by base of stump)
20" pine S5°E 125 LKS (now missing)

K-37B

1-52-R

Restoration:

Set 5/8" x 30" iron rod with 1 1/2" aluminum cap marked,
"Oregon State Parks".
Set steel post with 1/4 scratched on white paddle 2 ft.
north of iron rod.
25" pine N60°W 38.6 ft. scribed 1/4S30BTRS-691
22" pine S45°W 21.2 ft. scribed 1/4S31BT
Fence attached to SW side of 22" BT.
Parks corner tag on 25" BT.

Witnessed by:

J. Hollingsworth
R. Hemmer
R. DePuy
C. Middleton

QUARTER CORNER 31 and 32

Original:

Post (now missing)
10" fir N62°E 20 LKS (now 38" fir with "1/4" visible)
12" fir N54°W 44 LKS (now 23" stump with trace of scribe)

Restoration:

Set 5/8" x 30" iron rod with 1 1/2" aluminum cap marked,
"Oregon State Parks".
Set steel post with paddle marked, "OREGON STATE PARK
BOUNDARY Do Not Disturb," 2 ft. west of iron rod.
11" Tamarack S86°W 36.7 ft. scribed, "E1/4S31BTRS-691"
Parks corner tag on 11" BT.

Witnessed by:

R. Hemmer
R. DePuy
C. Middleton

CLOSING CORNER 31, 4 and 5

Original:

Stone 16" x 12" x 5" (found stone in place in mound of stone
with 4 notches on E. edge)
13" pine S59°E 82 LKS (now 28" pine face not uncovered with
Forest Service Corner tag)
28" pine S54°W 50 LKS (now a rotted stump. No scribe visible)

Witnessed by:

R. Hemmer
L. Boge
R. DePuy

CLOSING CORNER 31, 32 and 4

Original:

Section Corner 31, 32, 5 and 6
Stone 15" x 10" x 4" (now missing)
22" pine N55°E 23 LKS (now 38" fir "T3SR31ES32BT" visible)
22" pine S50°E 35 LKS (now 33" stump "BT" visible)
18" fir S71°W 20 LKS (now missing)
24" fir N56°W 43 LKS (now missing)

Restoration:

Found:
3/4" bolt with 1" square head in fence line.
Set steel post with paddle marked, "OREGON STATE PARK
BOUNDARY Do Not Disturb" 3 ft. N.W. of bolt.

Witnessed by:

R. Hemmer
R. DePuy
C. Middleton

NORTH SIXTEENTH BETWEEN 31 and 32

Established:

Set 5/8" x 30" iron rod with 1 1/2" aluminum cap marked,
"Oregon State Parks".
Set steel post with paddle marked, "OREGON STATE PARK
BOUNDARY Do Not Disturb"
18" fir S72 1/2°W 34.3 ft. scribed, "N 1/16S31BTRS691"
14" pine S10 1/2°E 63.0 ft. scribed, "N 1/16S32BT"
Parks corner tag on 18" BT.
2 1/2" iron pipe bears North 4.0 ft.
North-South fence bears East 4.5 ft.

SOUTH SIXTEENTH BETWEEN 31 and 32

Established:

Set 5/8" x 30" iron rod with 1 1/2" aluminum cap marked,
"Oregon State Parks".
Set steel post with paddle marked, "OREGON STATE PARK
BOUNDARY Do Not Disturb"
24" pipe N 18 1/2°W 42.3 ft. scribed, "S 1/16S31BTRS691"
12" fir N81°E 19.8 ft. scribed "S 1/16S32BT"
Parks corner tag on 24" BT.
North-South fence bears West 28.0 ft.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

John E. Hollingsworth

OREGON
JULY 9, 1965
JOHN E. HOLLINGSWORTH
691