


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

P-25

History of original corner establishment: Corner was originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 304, dated September 19, 1878. The original notes state that at the corner position a 18" x 12" x 4' stone was set on NW side of knoll from which:



- A Pine 10" dia bears N72°E 72 lk dist.
- A Fir 12" dia bears N20°W 53 lk dist.

Remonumentation was done in 1978 by BLM, see sheet 2 for record of BLM remonumentation.

Description of corner evidence found:

3" brass cap on 2 1/2" l. pipe in mound of stone from which:

- A 18" dia Fir Snag bears N20°W 35.5 ft dist - (old BT blaze open visible scribing.)
- A 12" dia Red Fir bears N73°W 30.3 ft dist tagged S73°E 46 lk dist - (recent blaze).
- A 12" dia Red Fir bears S29°W 13.0 ft dist tagged N 29½°E 20 lk dist - (recent blaze).

Description of monument and accessories I established to perpetuate the original location of this corner:


Set steel fence posts 5 ft North with 54-2 and 4 signs, 4 ft South with 54-2 sign. Blaze faces and 6" band around bearing trees was painted red. Trees tagged with 54-3 and 4 signs where needed.

Used steel tape and magnetic compass 19 3/4° East declination. Measured to the center of the BTs.

Corner was maintained on September 27, 1982.

Standard BLM cap. Cap marked:

Witnessed by: D. L. Kaufman PLS



REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of.....County Surveyor..... County of.....Umatilla.....
State of.....Oregon..... I hereby certify that the within instrument was filed in this office
for record on the 15th day of December, 1982
David H. Humber by *Billy A. Shatto*
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd By _____
No. 82-137-B

☆ GPO-798-276

History of 1978 BLM Remonumentation - (From BLM Field Notes)

The 1/4 sec. cor. of sec. 24 only, on the E. bdy. of the Tp., determined at record bearing and distance from the remains of an original bearing tree:

A Fir Snag, 21 ins. diam., bears N. 20° W., 53 lks. dist., with fragmentary scribe marks visible on open and decayed blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 22 ins. in the ground, and in a mound of stone, 3 ft. base, to top, with brass cap marked:

T3S
R31E | R32E
¼ S24 |
1978

from which new bearing trees

A Fir, 12 ins. diam., bears S. 29½° W., 20 lks. dist., mkd. ¼ S24 BT.

A Fir, 11 ins. diam., bears N. 73° W., 46 lks. dist., mkd. ¼ S24 BT.

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd by _____
No. 82-137-B