


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V-13

History of original corner establishment: Corner originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 319, dated March 26, 1879. The original notes state that at the corner a 17" x 8" x 7" basalt stone was set on South slope in small open from which:



- A 24" dia Pine bears N44°E 201 lk dist.
- A 20" dia Pine bears S28°E 149 lk dist.
- A 13" dia Pine bears S80°W 125 lk dist.

Corner remonumented in 1978 by BLM, see sheet 2 for history of BLM remonumentation.

**Description of corner evidence found:**

3" brass cap on 2 1/2" l. pipe protruding 8" from ground at edge of Rock Jack in fence corner from which:

- A 19" dia Ponderosa Pine bears S13°W 82.5 ft dist tagged N14°E 125 lk dist - (old BT, open blaze).
- A 13" dia Ponderosa Pine bears N54°W 27.4 ft dist tagged S54°E 41 lk dist - recent blaze.
- A 20" dia Ponderosa Pine bears N44°E 43.2 ft dist tagged S46°W 65 lk dist - recent blaze.
- A 14" dia Ponderosa Pine bears S73°E 48.7 ft dist tagged N73°W 74 lk dist - recent blaze.
- A 18" dia Pine Stump bears N38°E 129.7 ft dist tagged S38°W 129.7 ft dist - (old BT).

**Description of monument and accessories established to perpetuate the original location of this corner:**


Blaze faces and 6" bands around bearing trees are painted red. Tagged trees with 54-3 & 4 signs where needed. Set steel fence post with 54-4 sign attached, North of corner.

Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner maintained on October 7, 1982.

Standard BLM. Cap marked:

Witnessed by: Leslie E. Wilson



**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

*William R. Wells*

OREGON  
JULY 22, 1977  
**WILLIAM R. WELLS**  
1106

Office of.....County Surveyor..... County of..... Umatilla

State of..... Oregon....., I hereby certify that the within instrument was filed in this office

for record on the 17<sup>th</sup> day of December, 1982

*Daniel H. Krums* being by *Betty L. Shatto*

(COUNTY OFFICIAL)

(DEPUTY)

REC. IV L LY

Form R6-7100-57 (9/71)

Umatilla County SURV. REC.

Date \_\_\_\_\_

Rec'd By \_\_\_\_\_

No. 82-138-B

History of 1978 BLM Remonumentation - (From BLM Field Notes)

The cor. of secs. 27, 28, 33, and 34, determined at record distance from the remains of the original bearing trees:

A Sawed Pine Stump, 25 ins. diam., bears N. 44° E., 201 lks. dist., with scribe marks E S27 BT visible on open blaze.

A Pine, 22 ins. diam., bears S. 14° W., 125 lks. dist., with scribe marks T3S R31E S33 visible on open blaze. (Record, S. 80° W.)

At the corner point

Set an iron post, 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, with brass cap mkd.

T3S	R31E
S28	S27
S33	S34
1978	

from which new bearing trees

A Ponderosa Pine, 20 ins. diam., bears N. 46° E., 65 lks. dist., mkd. T3S R31E S27 BT.

A Ponderosa Pine, 14 ins. diam., bears S. 73° E., 74 lks. dist., mkd. T3S R31E S34 BT.

A Ponderosa Pine, 12 ins. diam., bears N. 54° W., 4s lks. dist., mkd. T3S R31E S28 BT.

RECEIVED BY  
Umatilla County Surv. yor  
Date \_\_\_\_\_  
Rec'd By \_\_\_\_\_  
No. 82-138-B