


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V-23

History of original corner establishment: Corner originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 319, dated March 26, 1879. The original notes state that at the corner a 18" x 10" x 5" basalt stone was set on SE face of hill from which:



- A 20" dia Pine bears S62°E 36 lk dist.
- A 16" dia Pine bears N28°W 52 lk dist.

No record of restoration appears in County Records.

Description of corner evidence found:

- A Pine Stump bears N23°W 34.32 ft dist - (old BT, with vague scribing badly decayed).
- A 28" dia Tamarack bears S60°E 23.76 ft dist - (old BT, partially healed blaze with visible scribing).


Description of monument and accessories I established to perpetuate the original location of this corner:

By record distance - distance intersect from original BTs, I set 2 1/2" brass cap on 2 1/2" x 30" l. pipe 18" in ground with mound of stone from which:

- A 10 1/2" dia Red Fir bears S46°W 72.4 ft dist marked: 1/4 S 36 BT.
- A 18" dia Red Fir bears N18 1/2°W 40.9 ft dist marked: 1/4 S25 BT.
- Blaze faces and 6" band around bearing trees are painted red. Trees tagged with 54 - 3 & 4 signs.
- Each new BT has lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush.
- Set steel fence post, with 54-2 & 4 signs attached, East of corner.
- Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner monumented on September 30, 1982.

Cap marked:



Witnessed by: Leslie E. Wilson

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County Surveyor..... County of..... Umatilla
State of..... Oregon..... I hereby certify that the within instrument was filed in this office
for record on the 15th day of November, 1982
Daniel H. Hummer by *Betty L. Slath*
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY 798-276

Umatilla County Surveyor
Date _____
Rec'd By _____
No. 82-137-B