

Index File No. W-16

T 35 R. 31E

Merid. Willamette

**CORNER RECORD (SEARCH)**

(Ref. FSM 7151.4)

R.D. Ukiah County Umatilla Tract or Survey No. Sec 34 Cor. No. NE 1/16

N.F. Umatilla State Oregon

**CORNER DIAGRAM**



T3S R31E  
NE 1/16  
S34

**DESCRIBE CORNER MONUMENT FOUND**

None.

**DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND**

None.

**PHOTO IDENTIFICATION DATA**

Photo No. \_\_\_\_\_  
Filed At. \_\_\_\_\_  
Object Ident. \_\_\_\_\_  
Ident. By \_\_\_\_\_  
*Signature*

**DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER**

Road #5420 to road #5412-100, then West on road #5412-100 approx. 1.7 miles to corner 100 ft Northeast of South timber line in Swiss Flat, and 30 ft Northeast of road across Swiss Flat.

**PLANE COORDINATE POSITION DATA**

State \_\_\_\_\_ Zone \_\_\_\_\_  
X \_\_\_\_\_  
Y \_\_\_\_\_  
Estab. By \_\_\_\_\_  
*Agency*

*Signature*  
William R. Wells

Title PLS 1106 Division \_\_\_\_\_ Headquarters \_\_\_\_\_

Date October 21, 1982 7100-52 (3, 68)

**CORNER RECORD (PERPETUATION)**

**MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

Set 2 1/2" brass cap on 2 1/2" x 30" l. pipe 6" in the ground with mound of stone.

T3S R31E  
NE 1/16

Set steel fence posts with 54-9 sign on one and 54-2 signs on both South and West of corner.  
Cap marked:

S34  
1982  
PLS 1106

**ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

A 20" dia Tamarack bears N84°W 136.2 ft dist marked: NE 1/16 S34 BT.

A 17" dia Tamarack bears S38°W 106.3 ft dist marked: NE 1/16 S34 BT.

Blaze faces and 6" bands around bearing trees are painted red. Tagged trees with 54-3 and 9 signs. BTs have a lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush.

Work Done By: W.R. Wells Title Surveyor Date 10/21/82 State Registration No. PLS 1106  
or Agency

Certified Cor. Record Prepared? Yes  No  Filed At: Umatilla County Surveyor Office Date

**REMARKS**

Witnessed by: D.L, Kaufman PLS  
R.D. English PC  
L.D. Henshaw  $\phi$   
L.E. Wilson  $\phi$